

LIST OF TESTING SERVICES AVAILABLE AT NTH(NER), GUWAHATI

Sl no	Region Name	Division	Material/Component/Product	Test Facilities	Specification	nabl	bis	approx_duration
1	GUWAHATI	RPPT	Textile	Dimensions general	IS 9	No	No	3 days
2	GUWAHATI	RPPT	Textile	Dimensions specific	IS 9	No	No	3 days
3	GUWAHATI	RPPT	Textile	Weight per square meter	IS 1964	No	No	3 days
4	GUWAHATI	RPPT	Textile	Moisture content	Relevant	No	No	3 days
5	GUWAHATI	RPPT	Textile	Bursting strength (normal/Wet)	Relevant	No	No	3 days
6	GUWAHATI	RPPT	Textile	Tearing strength (Warp / weft)	Relevant	No	No	3 days
7	GUWAHATI	RPPT	Textile	Moisture regain test	Relevant	No	No	3 days
8	GUWAHATI	RPPT	Textile	Relaxation shrinkage test	Relevant	No	No	5 days
9	GUWAHATI	RPPT	Textile	Ends & picks	IS 1963	No	No	3 days
10	GUWAHATI	RPPT	Textile	Pilling Test	Relevant	No	No	3 days
11	GUWAHATI	RPPT	Bitumen felt	Weight /Unit area	Relevant	No	No	3 days
12	GUWAHATI	RPPT	Bitumen felt	Softening point of bitumen	Relevant	No	No	5 days
13	GUWAHATI	RPPT	Bitumen felt	Penetration of recovered bitumen	Relevant	No	No	5 days
14	GUWAHATI	RPPT	Bitumen felt	Water absorption test	Relevant	No	No	5 days
15	GUWAHATI	RPPT	Bitumen felt	Heat resistance test	Relevant	No	No	5 days
16	GUWAHATI	Chemical	Metal & Alloys	Carbon Steel-5 element	IS 2062	Yes	No	5 days
17	GUWAHATI	Chemical	Metal & Alloys	Carbon Steel with micro elements	IS 2062	Yes	No	5 days
18	GUWAHATI	Chemical	Metal & Alloys	HSDS Bar (C,S,P, & S+P)	IS 1786	Yes	No	5 days
19	GUWAHATI	Chemical	Metal & Alloys	HSDS Bar with micro-alloying elements	IS 1786	Yes	No	5 days
20	GUWAHATI	Chemical	Metal & Alloys	Stainless Steel & Tool Steel	Relevant	Yes	No	5 days
21	GUWAHATI	Chemical	Metal & Alloys	Ferrous & Non Ferrous, Ores, Minerals & Alloys complete analysis	Relevant	No	No	5 days
22	GUWAHATI	Chemical	Metal & Alloys	OTHER INDIVIDUAL ELEMENTS pertaining to Ferrous & Non Ferrous, Ores, Minerals & Alloys	Relevant	No	No	5 days
23	GUWAHATI	Chemical	Metal & Alloys	Anodic Coating on Aluminium ALLOY	IS 5523	No	No	5 days
24	GUWAHATI	Chemical	Metal & Alloys	Galvanization (Mass & Uniformity of zinc coating)	Relevant	No	No	5 days
25	GUWAHATI	Chemical	Metal & Alloys	Elements (Ferrous & non-ferrous) by OES Method Complete analysis upto 5-element. (each additional element Rs.500/-)	Relevant	Yes	No	5 days
26	GUWAHATI	Chemical	Metal & Alloys	Elements (Ferrous & non-ferrous) by OES Method per Individual element		Yes	No	5 days
27	GUWAHATI	Chemical	Building Materials	Cement all type	IS 269/8112	Yes	No	10 days
28	GUWAHATI	Chemical	Building Materials	Concrete mixing ratio / cement mortar/	IS 1489/	No	No	10 days
29	GUWAHATI	Chemical	Building Materials	Deleterious material	IS 3812	No	No	10 days
30	GUWAHATI	Chemical	Building Materials	Deleterious materials	Relevant	No	No	10 days
31	GUWAHATI	Chemical	Building Materials	Chloride content ,	Relevant	No	No	10 days
32	GUWAHATI	Chemical	Building Materials	Identification of Adhesive	Relevant	No	No	10 days
33	GUWAHATI	Chemical	Building Materials	Lime & Lime stone (chemical tests)	Relevant	No	No	10 days
34	GUWAHATI	Chemical	Building Materials	Cement Concrete	ASTM	No	No	10 days
35	GUWAHATI	Chemical	Building Materials	Bleaching Powder	IS 1065	No	No	5 days
36	GUWAHATI	Chemical	Building Materials	Fly Ash	IS 3812	No	No	10 days
37	GUWAHATI	Chemical	Building Materials	Sand General Chemical Analysis	IS 383, 2386	No	No	10 days
38	GUWAHATI	Chemical	Building Materials	Estimation of Alkalies (Sodium & Potassium Oxide) water soluble	Relevant	No	No	5 days
39	GUWAHATI	Chemical	WATER & DISINFECTANT	Water for construction use Chemical Tests	IS 456	No	No	5 days
40	GUWAHATI	Chemical	WATER & DISINFECTANT	Drinking Water	IS 10500	Yes	No	10 days
41	GUWAHATI	Chemical	WATER & DISINFECTANT	Water Bacteriological Examination (Coliform organism)	IS 10500	No	No	5 days
42	GUWAHATI	Chemical	WATER & DISINFECTANT	Water for Marine Boilers	IS 1813	No	No	10 days
43	GUWAHATI	Chemical	WATER & DISINFECTANT	Water for Swimming Pools	IS 3328	No	No	10 days
44	GUWAHATI	Chemical	WATER & DISINFECTANT	Industrial Effluent Water up to 6 Test	IS 2490 P-1	No	No	10 days
45	GUWAHATI	Chemical	WATER & DISINFECTANT	Industrial Effluent inorganic/organic elements/ Compounds (Qualitative/ Quant.)	Relevant	No	No	10 days
46	GUWAHATI	Chemical	WATER & DISINFECTANT	BOD in effluent water	Relevant	No	No	10 days
47	GUWAHATI	Chemical	WATER & DISINFECTANT	COD in effluent water	Relevant	No	No	10 days
48	GUWAHATI	Chemical	WATER & DISINFECTANT	Packaged Drinking Water (Excluding residual PCB,PAH & Radio active substance	IS 14528	No	No	10 days
49	GUWAHATI	Chemical	WATER & DISINFECTANT	UV/Visible Spectral Analysis per Compound	UV-VIS	No	No	5 days

50	GUWAHATI	Chemical	WATER & DISINFECTANT	GCMS Spectral Study	GCMS	No	No	10 days
51	GUWAHATI	Chemical	WATER & DISINFECTANT	GCMS Spectral Study after separation / comp.	GCMS	No	No	5 days
52	GUWAHATI	Chemical	MISCELLANEOUS	Acidity	Relevant	No	No	2 days
53	GUWAHATI	Chemical	MISCELLANEOUS	Ash	Relevant	No	No	2 days
54	GUWAHATI	Chemical	MISCELLANEOUS	Aluminium	Relevant	No	No	2 days
55	GUWAHATI	Chemical	MISCELLANEOUS	Copper or Zinc	Relevant	No	No	5 days
56	GUWAHATI	Chemical	MISCELLANEOUS	pH	Relevant	No	No	2 days
57	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Consistency	IS 269	Yes	No	3 days
58	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Fineness by Blaine's Apparatus (Including Specific gravity)	IS 269	Yes	No	3 days
59	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Setting Time	IS 269	Yes	No	3 days
60	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Soundness by Le Chatlier's method	IS 269	Yes	No	5 days
61	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Soundness by autoclave method	IS 269	Yes	No	5 days
62	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Compressive Strength (3 duration)	IS 269	Yes	No	40 days
63	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Drying Shrinkage	IS 1489	Yes	No	45 days
64	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Particle retained on 45 micron sieve	IS 269	Yes	No	3 days
65	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Compressive Strength 2 durations	IS 269	Yes	No	10 days
66	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Specific Gravity of Cement	IS 269	Yes	No	3 days
67	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	33 Gr OPC -Full test	IS 269	Yes	No	40 days
68	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	43 Gr OPC -Full test	IS 269	Yes	No	40 days
69	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	53 Gr OPC -Full test	IS 269	Yes	No	40 days
70	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Portland Slag Cement -Full test	IS 455	Yes	No	40 days
71	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Portland Pozzolana Cement-Full test	IS 1489(Pt-1,2)	Yes	No	45 days
72	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	White Portland Cement - Full test	IS 8042	No	No	45 days
73	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Rapid hardening portland cement - Full test	IS 8041	No	No	40 days
74	GUWAHATI	Civil	CEMENT AND ALLIED PRODUCTS	Chemical Analysis for Cement	IS 1727	Yes	No	15 days
75	GUWAHATI	Civil	Pulverized Fuel Ash - Full test	Fineness by Blaine's Apparatus (including Specific Gravity)	IS 3812	No	No	3 days
76	GUWAHATI	Civil	Pulverized Fuel Ash - Full test	Drying Shrinkage	IS 3812	No	No	45 days
77	GUWAHATI	Civil	Pulverized Fuel Ash - Full test	Lime reactivity	IS 3812	No	No	15 days
78	GUWAHATI	Civil	Pulverized Fuel Ash - Full test	Compressive Strength of Fly ash(comparative)	IS 3812	No	No	40 days
79	GUWAHATI	Civil	Pulverized Fuel Ash - Full test	Soundness by autoclave expansion of Fly ash	IS 3812	No	No	5 days
80	GUWAHATI	Civil	Pulverized Fuel Ash - Full test	Particle retained on 45 micron sieve	IS 3812	No	No	5 days
81	GUWAHATI	Civil	Pulverized Fuel Ash - Full test	Setting time	IS 3812	No	No	5 days
82	GUWAHATI	Civil	Pulverized Fuel Ash - Full test	Chemical Analysis for fly ash	IS 1727	No	No	10 days
83	GUWAHATI	Civil	Pulverized Fuel Ash - Full test	Pulverized Fuel Ash - Full test	IS 3812	No	No	45 days
84	GUWAHATI	Civil	Water Proofing Compounds	Setting Time for WPC	IS 2645	No	No	4 days
85	GUWAHATI	Civil	Water Proofing Compounds	Compressive Strength for WPC	IS 2645	No	No	12 days
86	GUWAHATI	Civil	BRICKS / BLOCKS	Visual Examination	IS 1077/2185	Yes	No	3 days
87	GUWAHATI	Civil	BRICKS / BLOCKS	Dimensions	IS 1077/2185	Yes	No	3 days
88	GUWAHATI	Civil	BRICKS / BLOCKS	Crushing Strength	IS 1077/2185	Yes	No	3 days
89	GUWAHATI	Civil	BRICKS / BLOCKS	Water Absorption	IS 1077/2185	Yes	No	3 days
90	GUWAHATI	Civil	BRICKS / BLOCKS	Efforescence	IS 1077/2185	Yes	No	10 days
91	GUWAHATI	Civil	BRICKS / BLOCKS	Dimensionss & Thickness	IS 1077/2185	Yes	No	3 days
92	GUWAHATI	Civil	BRICKS / BLOCKS	Compressive Strength for Pavers/Blocks	IS 1077/2185/15658	Yes	No	4 days
93	GUWAHATI	Civil	BLOCKS	Abrasion Resistance for pavers	IS 15658	Yes	No	7 days
94	GUWAHATI	Civil	BLOCKS	Block Density for hollow blocks/Cellular block	IS 2185	No	No	3 days
95	GUWAHATI	Civil	BLOCKS	Moisture Content for hollow blocks/cellular block	IS 2185	No	No	3 days
96	GUWAHATI	Civil	BLOCKS	Compressive Strength per cellular block	IS 2185	No	No	4 days
97	GUWAHATI	Civil	BRICKS	Burnt Clay Building Bricks -Full test	IS 1077	Yes	No	15 days
98	GUWAHATI	Civil	BRICKS	Pulverized Fuel Ash Lime Bricks -Full test	IS 12894	Yes	No	15 days
99	GUWAHATI	Civil	BLOCKS	Paving Blocks - Obligatory tests (Dimensions, Water Absorption, Compressive Strength, abrasion (dry & wet conditions))	IS 15658	Yes	No	10 days
100	GUWAHATI	Civil	BLOCKS	Hollow Concrete Blocks -Full test	IS 2185	No	No	7 days
101	GUWAHATI	Civil	BLOCKS	AAC Blocks (Except Drying Shrinkage & Thermal Conductivity)	IS 2185 (P 3)	No	No	10 days
102	GUWAHATI	Civil	STONES /ROCKS	Water absorption	IS 1124	No	No	3 days
103	GUWAHATI	Civil	STONES /ROCKS	Specific Gravity of rock	IS 1122	No	No	3 days
104	GUWAHATI	Civil	STONES /ROCKS	Density (Boulders,stone)	IS 1122	No	No	3 days
105	GUWAHATI	Civil	STONES /ROCKS	Specific Weight (Boulders/Blocks)	IS 1122	No	No	3 days
106	GUWAHATI	Civil	STONES /ROCKS	Structural Granite -Partial test	IS 3316	No	No	7 days
107	GUWAHATI	Civil	CONCRETE	Compressive Strength of CC Cube 1 set	IS 516	Yes	No	5 days

108	GUWAHATI	Civil	CONCRETE	Equivalent Cube Strength of Concrete core 1 set	IS 516	Yes	No	7 days
109	GUWAHATI	Civil	CONCRETE	Concrete Mix Design	IS 10262	No	No	50 days
110	GUWAHATI	Civil	CONCRETE	Concrete Mix Design (with admixture)	IS 10262	No	No	50 days
111	GUWAHATI	Civil	CONCRETE	Compressive Strength of Cube/Block with preparation	IS 516	Yes	No	3 days
112	GUWAHATI	Civil	CONCRETE	Preparation of core	IS 516	Yes	No	2 days
113	GUWAHATI	Civil	CONCRETE	Slump test	IS 10262	No	No	3 days
114	GUWAHATI	Civil	WATER	Setting time of water sample	IS 456	No	No	3 days
115	GUWAHATI	Civil	WATER	Compressive strength of water sample	IS 456	No	No	40 days
116	GUWAHATI	Civil	WATER	Water for construction - Full test	IS 456	No	No	40 days
117	GUWAHATI	Civil	TILES	Dimensions & Visual examination	IS 15622	No	No	3 days
118	GUWAHATI	Civil	TILES	Water Absorption	IS 15622	No	No	5 days
119	GUWAHATI	Civil	TILES	Dimensions Length ceramic tiles	IS 15622	No	No	3 days
120	GUWAHATI	Civil	TILES	Dimensions Width ceramic tiles	IS 15622	No	No	3 days
121	GUWAHATI	Civil	TILES	Dimensions Thickness ceramic tiles	IS 15622	No	No	3 days
122	GUWAHATI	Civil	TILES	Modulus of Rupture ceramic tiles	IS 15622	No	No	5 days
123	GUWAHATI	Civil	TILES	Breaking Strength ceramic tiles	IS 15622	No	No	5 days
124	GUWAHATI	Civil	TILES	C.C.Flooring Tiles	IS 1237	No	No	10 days
125	GUWAHATI	Civil	TILES	Chequered CC Flooring Tiles -Full	IS 13801	No	No	12 days
126	GUWAHATI	Civil	TILES	Ceramic tiles - Partial test	IS 15622	No	No	14 days
127	GUWAHATI	Civil	TILES	Acid Resistance-Partial	IS 4457	No	No	14 days
128	GUWAHATI	Civil	AGGREGATES	Grading and fineness Modulus	IS 383	Yes	No	5 days
129	GUWAHATI	Civil	AGGREGATES	Aggregate Crushing Value	IS 383	Yes	No	5 days
130	GUWAHATI	Civil	AGGREGATES	Aggregate Impact Value	IS 383	Yes	No	5 days
131	GUWAHATI	Civil	AGGREGATES	Aggregate Abrasion Value	IS 383	Yes	No	5 days
132	GUWAHATI	Civil	AGGREGATES	Soundness	IS 383	Yes	No	10 days
133	GUWAHATI	Civil	AGGREGATES	Deleterious Materials and Organic impurities	IS 383	Yes	No	5 days
134	GUWAHATI	Civil	AGGREGATES	Specific Gravity	IS 383	Yes	No	3 days
135	GUWAHATI	Civil	AGGREGATES	Loose Bulk Density	IS 383		No	3 days
136	GUWAHATI	Civil	AGGREGATES	Compacted Bulk Density	IS 383		No	3 days
137	GUWAHATI	Civil	AGGREGATES	Water absorption	IS 383	Yes	No	5 days
138	GUWAHATI	Civil	AGGREGATES	Silt content (CPWD Specification)	IS 383	Yes	No	3 days
139	GUWAHATI	Civil	AGGREGATES	Flakiness Index	IS 383	Yes	No	5 days
140	GUWAHATI	Civil	AGGREGATES	Elongation Index	IS 383	Yes	No	5 days
141	GUWAHATI	Civil	AGGREGATES	Moisture content	IS 383		No	3 days
142	GUWAHATI	Civil	AGGREGATES	Coarse aggregate -Full test	IS 383	Yes	No	20 days
143	GUWAHATI	Civil	AGGREGATES	Fine Aggregate - Full test	IS 383	Yes	No	15 days
144	GUWAHATI	Civil	A.C.SHEETS	Dimenion and Visual examination of A.C.Sheets	IS 459	No	No	4 days
145	GUWAHATI	Civil	A.C.SHEETS	Density	IS 459	No	No	3 days
146	GUWAHATI	Civil	A.C.SHEETS	Impermeability test of A.C.Flat Sheet	IS 459	No	No	3 days
147	GUWAHATI	Civil	A.C.SHEETS	Water absorption (Single duration)	IS 459	No	No	5 days
148	GUWAHATI	Civil	A.C.SHEETS	Load Bearing capacity of A.C.Sheet	IS 459	No	No	5 days
149	GUWAHATI	Civil	A.C.SHEETS	Moisture Content	IS 459	No	No	5 days
150	GUWAHATI	Civil	A.C.SHEETS	Water absorption	IS 459	No	No	5 days
151	GUWAHATI	Civil	A.C. Boards	Asbestos cement building board Partial test	IS 2098	No	No	7 days
152	GUWAHATI	MECHANICAL TESTING	Galvanised Tubes	Visual Examination	IS 1161	NO	NO	2 DAYS
153	GUWAHATI	MECHANICAL TESTING	Galvanised Tubes	Tensile test	IS 1161	YES	NO	5 DAYS
154	GUWAHATI	MECHANICAL TESTING	Galvanised Tubes	Dimensions	IS 1161	NO	NO	2 DAYS
155	GUWAHATI	MECHANICAL TESTING	Galvanised Tubes	Mass	IS 1161	NO	NO	2 DAYS
156	GUWAHATI	MECHANICAL TESTING	Galvanised Tubes	Bend test /Flattening	IS 1161	NO	NO	2 DAYS
157	GUWAHATI	MECHANICAL TESTING	Galvanised Tubes	Chemical analysis	IS 1161	YES	NO	5 DAYS
158	GUWAHATI	MECHANICAL TESTING	Galvanised Tubes	Galvanisation	IS 1161	NO	NO	5 DAYS
159	GUWAHATI	MECHANICAL TESTING	G.I. pipes	Visual Examination	IS 1239 (Part 1)	NO	NO	2 DAYS
160	GUWAHATI	MECHANICAL TESTING	G.I. pipes	Tensile test	IS 1239 (Part 1)	YES	NO	5 DAYS
161	GUWAHATI	MECHANICAL TESTING	G.I. pipes	Dimensions	IS 1239 (Part 1)	NO	NO	2 DAYS
162	GUWAHATI	MECHANICAL TESTING	G.I. pipes	Mass	IS 1239 (Part 1)	NO	NO	2 DAYS
163	GUWAHATI	MECHANICAL TESTING	G.I. pipes	Bend test /Flattening	IS 1239 (Part 1)	NO	NO	2 DAYS
164	GUWAHATI	MECHANICAL TESTING	G.I. pipes	Chemical analysis	IS 1239 (Part 1)	YES	NO	5 DAYS
165	GUWAHATI	MECHANICAL TESTING	G.I. pipes	Galvanisation	IS 1239 (Part 1)	NO	NO	5 DAYS
166	GUWAHATI	MECHANICAL TESTING	HSD Bar (0-12 mm)	Mass per meter run	IS 1786	YES	NO	2 DAYS
167	GUWAHATI	MECHANICAL TESTING	HSD Bar (0-12 mm)	Tensile test	IS 1786	YES	NO	5 DAYS
168	GUWAHATI	MECHANICAL TESTING	HSD Bar (0-12 mm)	Bend test	IS 1786	YES	NO	2 DAYS
169	GUWAHATI	MECHANICAL TESTING	HSD Bar (0-12 mm)	Rebend test	IS 1786	YES	NO	2 DAYS
170	GUWAHATI	MECHANICAL TESTING	HSD Bar (0-12 mm)	Rib area	IS 1786	NO	NO	2 DAYS

171	GUWAHATI	MECHANICAL TESTING	HSD Bar (0-12 mm)	Chemical analysis	IS 1786	YES	NO	5 DAYS
172	GUWAHATI	MECHANICAL TESTING	HSD Bar (12 - 28 mm)	Mass per meter run	IS 1786	YES	NO	2 DAYS
173	GUWAHATI	MECHANICAL TESTING	HSD Bar (12 - 28 mm)	Tensile test	IS 1786	YES	NO	3 DAYS
174	GUWAHATI	MECHANICAL TESTING	HSD Bar (12 - 28 mm)	Bend test	IS 1786	YES	NO	2 DAYS
175	GUWAHATI	MECHANICAL TESTING	HSD Bar (12 - 28 mm)	Rebend test	IS 1786	YES	NO	2 DAYS
176	GUWAHATI	MECHANICAL TESTING	HSD Bar (12 - 28 mm)	Rib area	IS 1786	NO	NO	2 DAYS
177	GUWAHATI	MECHANICAL TESTING	HSD Bar (12 - 28 mm)	Chemical analysis	IS 1786	YES	NO	5 DAYS
178	GUWAHATI	MECHANICAL TESTING	HSD Bar (28 -32 mm)	Mass per meter run	IS 1786	YES	NO	2 DAYS
179	GUWAHATI	MECHANICAL TESTING	HSD Bar (28 -32 mm)	Tensile test	IS 1786	YES	NO	5 DAYS
180	GUWAHATI	MECHANICAL TESTING	HSD Bar (28 -32 mm)	Bend test	IS 1786	YES	NO	2 DAYS
181	GUWAHATI	MECHANICAL TESTING	HSD Bar (28 -32 mm)	Rebend test	IS 1786	YES	NO	2 DAYS
182	GUWAHATI	MECHANICAL TESTING	HSD Bar (28 -32 mm)	Rib area	IS 1786	NO	NO	2 DAYS
183	GUWAHATI	MECHANICAL TESTING	HSD Bar (28 -32 mm)	Chemical analysis	IS 1786	YES	NO	5 DAYS
184	GUWAHATI	MECHANICAL TESTING	Structural Steel	Visual Examination	IS 2062	NO	NO	2 DAYS
185	GUWAHATI	MECHANICAL TESTING	Structural Steel	Tensile test	IS 2062	YES	NO	5 DAYS
186	GUWAHATI	MECHANICAL TESTING	Structural Steel	Bend test(upto 25 mm)	IS 2062	YES	NO	2 DAYS
187	GUWAHATI	MECHANICAL TESTING	Structural Steel	Bend test (above 25 mm)	IS 2062	YES	NO	2 DAYS
188	GUWAHATI	MECHANICAL TESTING	Steel Tubes	Visual Examination	IS 3601	NO	NO	2 DAYS
189	GUWAHATI	MECHANICAL TESTING	Steel Tubes	Dimensions	IS 3601	NO	NO	2 DAYS
190	GUWAHATI	MECHANICAL TESTING	Steel Tubes	Tensile test	IS 3601	YES	NO	5 DAYS
191	GUWAHATI	MECHANICAL TESTING	Steel Tubes	Bend test /Flattening	IS 3601	NO	NO	2 DAYS
192	GUWAHATI	MECHANICAL TESTING	Steel Tubes	Chemical analysis	IS 3601	YES	NO	5 DAYS
193	GUWAHATI	MECHANICAL TESTING	Steel tubes for Water Wells	Visual Examination	IS 4270	NO	NO	3 DAYS
194	GUWAHATI	MECHANICAL TESTING	Steel tubes for Water Wells	Dimensions	IS 4270	NO	NO	3 DAYS
195	GUWAHATI	MECHANICAL TESTING	Steel tubes for Water Wells	Tensile test	IS 4270	YES	NO	3 DAYS
196	GUWAHATI	MECHANICAL TESTING	Steel tubes for Water Wells	Bend test /Flattening	IS 4270	NO	NO	3 DAYS
197	GUWAHATI	MECHANICAL TESTING	Steel tubes for Water Wells	Chemical analysis	IS 4270	YES	NO	5 DAYS
198	GUWAHATI	MECHANICAL TESTING	Hot rolled steel rivet bar	Tensile test	IS 1148	YES	NO	5 DAYS
199	GUWAHATI	MECHANICAL TESTING	Hot rolled steel rivet bar	Bend test	IS 1148	NO	NO	2 DAYS
200	GUWAHATI	MECHANICAL TESTING	Hot rolled steel rivet bar	Chemical analysis	IS 1148	YES	NO	5 DAYS
201	GUWAHATI	MECHANICAL TESTING	High Tensile steel rivet bar	Dimensions	IS 1149	NO	NO	2 DAYS
202	GUWAHATI	MECHANICAL TESTING	High Tensile steel rivet bar	Tensile test	IS 1149	YES	NO	5 DAYS
203	GUWAHATI	MECHANICAL TESTING	High Tensile steel rivet bar	Bend test	IS 1149	NO	NO	2 DAYS
204	GUWAHATI	MECHANICAL TESTING	High Tensile steel rivet bar	Chemical analysis	IS 1149	YES	NO	5 DAYS
205	GUWAHATI	MECHANICAL TESTING	Hollow steel section for structural use	Dimensions	IS 4923	NO	NO	2 DAYS
206	GUWAHATI	MECHANICAL TESTING	Hollow steel section for structural use	Weight	IS 4923	NO	NO	2 DAYS
207	GUWAHATI	MECHANICAL TESTING	Hollow steel section for structural use	Tensile	IS 4923	YES	NO	5 DAYS
208	GUWAHATI	MECHANICAL TESTING	Hollow steel section for structural use	Chemical analysis	IS 4923	YES	NO	5 DAYS
209	GUWAHATI	MECHANICAL TESTING	Seamless / ERW Steel pipes	Dimensions	IS 3589	NO	NO	2 DAYS
210	GUWAHATI	MECHANICAL TESTING	Seamless / ERW Steel pipes	Visual inspection	IS 3589	NO	NO	2 DAYS
211	GUWAHATI	MECHANICAL TESTING	Seamless / ERW Steel pipes	Workmanship	IS 3589	NO	NO	2 DAYS
212	GUWAHATI	MECHANICAL TESTING	Seamless / ERW Steel pipes	Mass	IS 3589	NO	NO	2 DAYS
213	GUWAHATI	MECHANICAL TESTING	Seamless / ERW Steel pipes	Tensile	IS 3589	YES	NO	5 DAYS
214	GUWAHATI	MECHANICAL TESTING	Seamless / ERW Steel pipes	Flattening test	IS 3589	NO	NO	3 DAYS
215	GUWAHATI	MECHANICAL TESTING	Seamless / ERW Steel pipes	Chemical analysis	IS 3589	YES	NO	5 DAYS